

Dipl.-Ing. Benjamin Beck
Chair of Fluid-Mechatronic Systems | TU Dresden

Joint research project „Bauen 4.0“

Overview, development status, demos and outlook

CMM online // December 2020

Outline

1. Overview 2. Development status 3. Demos 4. Outlook

1. Overview

2. Demos

3. Development status

4. Outlook


Project partners and organizational framework

Facts and Figures:


- Funding BMBF – Project Management Agency Karlsruhe – INKOWE program
- Duration July 2019 – July 2022
- 20 industrial partners, 2 universities
- Accompanied by various associations
- Total costs 9 Mio. € / 4,8 Mio. € funding



Construction Site Problems



The main topics



Automated, connected mobile machines

- Automation
- Assistance functions
- Remote control
- Environment recognition
- Vertical Integration



5G machine and construction site connectivity

- Connectivity Solutions
- Cloud Technologies
- Reliable and secure data exchange



Processes and solutions for the digital construction site

- Tracking & Tracing
- Simulation of construction processes
- BIM to BIMsite
- Driver guidance system 4.0

Sustainable demonstration & development platform for industry 4.0 solutions in construction site operations: Common Demo Scenario for 2022

2. Demos

Demos within the main topics



Automated, connected mobile machines

Vertical Integration via OPC UA

- Automated digging
- Automated tool change
- Detection "as built" condition
- Automated driving
- Environment recognition
- Automated processes
- Remote Control



5G machine and construction site connectivity


- Mult-Connectivity modul: WiFi, 5G, 4G, BLE...



- Construction Site Networks: WiFi, 5G Campus



- Distributed Cloud Services



Processes and solutions for the digital construction site

- Tracking & Tracing of Material via LPWAN




- Process optimization and progress prediction using simulation and machine data (e.g. with ISO 15143-3 data via OPC UA)



- AR-based driver assistance: Visualization via HoloLens




Demo Scenario at project end in 2022



3. Development Status


Use Cases and data exchange requirements

- Accompanying process simulation during construction with a rotary drilling rig
- Model-based, automated earthworks and acquisition of actual condition / surface model by excavator
- Order transmission and automation of the movement of a loading crane
- Automated driving with a wheel loader
- Digital twin of the excavator for anomaly detection based on operational data
- Flexible site networks (5G, campus networks, mesh network, MEC)
- Tracking and tracing of attachments, material, bulk materials, auxiliary equipment




➔ **Various latency and data rate requirements**

Connectivity Architecture




Focus on construction site layer – an independent local solution

Overall Architecture





Excavator -
A source of information on
the construction site

OPC-UA-architecture




OPC-UA data model for construction equipment

- Apply **basic building blocks for machinery** (finding machines on server and identification)
- Describe construction equipment as **Robotics:MotionDeviceType**
- Extending robotics CS for **full kinematic description** to enable forward kinematic calculation and visualization
- Equipment Telematics-interface to feature **telematics data** records from ISO 15143-3



First Implementation tests: OPC-UA based Remote Diagnosis via ISO 15143-3 data



4. Outlook

Next Steps

2020



- Scaling the Lab Demo: More Machines
- Setting Up Local Site Server
- Integration of Applications

 Fabrikstraße 48, Dresden

2021




- WiFi to 5G Campus
- Setting up Remote Control Use Cases

 Industriegebiet Zeißig, Hoyerswerda

2022



- Preparation Demo Scenario
- Development of infrastructure and organizational forms for use after project end

 Gewerbegebiet Klingewalde, Görlitz

Publications

- Fischer, A. et al.: Begleitende Prozesssimulation für das Kellybohrverfahren. In Proceedings of „8.Fachtagung Baumaschinentechnik“, Dresden, 2020
- Köhler, S. et al.: Netzwerkschnittstellen für mobile Arbeitsmaschinen im Kontext der digitalisierten Baustelle. In Proceedings of „8.Fachtagung Baumaschinentechnik“, Dresden, 2020
- Schöberl, M. et al.: The Process-oriented Digital Twin of Construction Machinery. In Proceedings of „8.Fachtagung Baumaschinentechnik“, Dresden, 2020
- Zitterbart, T.: Anbauwerkzeug wird zum IoT-Device. In Proceedings of „8.Fachtagung Baumaschinentechnik“, Dresden, 2020
- Beck, B. et al.: Connected Off-Highway Machines and Services – Large Scale Lab-Demonstrator Activities. Video Contribution to 5G++ Online Summit, Dresden, 2020
- Zhang, Jiajing; Kharabet, Ievgen: SENCE - Solution for Extended Network in Construction Environment. Video Contribution to 5G++ Online Summit, Dresden, 2020
- Waurich, V.; Will, F.: The Role of Construction Machinery on an Automated and Connected Construction Site. White Paper within 4th International VDI Conference “Smart Construction Equipment”, München, 2020

Abstracts/presentations accepted for [Mobile Machines April 2021](#); [ISIC-Webinar September 2021](#); [CECE Digitalisation Task Force Meeting January 2021](#); [European Conference on Computing in Construction EC³ July 2021](#)

SPONSORED BY THE



Federal Ministry
of Education
and Research

MANAGED BY



PTKA

Project Management Agency Karlsruhe

Karlsruhe Institute of Technology

contact

Dipl.-Ing. Benjamin Beck

Chair of Fluid-Mechatronic Systems

✉ : Benjamin.beck@tu-dresden.de

☎ : +49 351 - 463 33559



SCAN ME

<https://verbundprojekt-bauen40.de/>



@bauen40